

Project/Program Name	Location	Scope Of Work	County	Financier	Estimated Project Cost	Contractor	Start Date	Completion Date	Beneficiary WSP	Current Status
Kerugoya-Kutus Water supply project	Kerugoya and Kutus	Intake Works at Kiringa and Thiba Rivers, Treatment Works of 30,000M3/Day, Raw water mains, 3 No. Storage Tanks, 63 Km Treated water Transmission and Distribution Mains ranging from 600mm to 150mm	Kirinyaga	ADB/GOK	1,159,898,600	Nanchang Municipal Engineering Development Group Company Limited/Nanchang Foreign Engineering Company (Kenya) Limited JV	11/01/2018	05/01/2021	Kirinyaga Water and Sanitation Company	Contractor Mobilisation
Kerugoya-Kutus Sewerage project	Kerugoya and Kutus	Trunk and Secondary Sewers 34 km ranging from Diameter 225 mm-675mm and Sewerage treatment works capacity 4000m3/day	Kirinyaga	ADB/GOK	500,139,446	Zhonghao Limited	11/01/2018	05/01/2021	Kirinyaga Water and Sanitation Company	Contractor Mobilisation
Chuka Water Project	Chuka	Intake Works at Ruguti River, Treatment Works 7500 M3/Day, Distribution Tanks and 27 Km of Raw Water and Treated water mains km Ranging from 450mm-140mm	Tharaka-Nithi	ADB/GOK	580,000,000	Not awarded	Not Started	Not Started	Nithi Water and Sanitation Company	In tendering stage
Chuka Sewerage project	Chuka	Trunk sewer 39 km dia ranging from 300-375mm, Secondary sewers 30 km Dia 225mm, Sewerage treatment works capacity-1100m3/day	Tharaka-Nithi	ADB/GOK	459,368,692	Zhonghao Limited	01/02/2019	07/02/2021	Nithi Water and Sanitation Company	Contractor Mobilisation
Chogoria Water supply project	Chogoria	Intake Works at Maara Manyi River, Treatment Works of 15,000 M3, 3 Km Raw Water Gravity main, 2 No Storage Tanks and 15 Km Treated water gravity mains km ranging from 450mm-150mm	Tharaka-Nithi	ADB/GOK	574,317,060	Oriental Construction	01/02/2019	01/02/2022	Nithi Water and Sanitation Company	Contractor Mobilisation
Chogoria Sewerage project	Chogoria	Trunk sewer 15.4 km dia ranging from 300-375mm, Secondary sewers 11 km Dia 225mm, Sewerage treatment works capacity-1100m3/day	Tharaka-Nithi	ADB/GOK	374,595,276	Zhonghao Limited	01/02/2019	07/02/2021	Nithi Water and Sanitation Company	Contractor Mobilisation
Mandera Water supply project (Co-ordination)	Mandera	Intake Works at Daua River, 5 No. Infiltration Wells, Treatment Works of 16,000 M3/Day, 9 No. Storage Tanks, 316 Km Treated water Transmission and Distribution Mains ranging from 500mm-63mm	Mandera	ADB/GOK	1,420,147,043	Suhufi Agencies/Shaanxi Water JV	31/1/2019	31/7/2021	Mandera Water and Sanitation Company	Contractor Mobilisation
Mandera Sewerage project (Co-ordination)	Mandera	Trunk sewer 4.3km dia 900mm, Secondary sewers 51.2km ranging from Dia 450mm – 225mm, Sewerage treatment works capacity 7000m3/day	Mandera	ADB/GOK	1,039,413,014	Sino Hydro Corporation	11/01/2018	05/01/2021	Mandera Water and Sanitation Company	Construction works is at 5%.
Marsabit Water supply project	Marsabit	7 km Dia 200mm rising main Treatment Works of 1,300 M3/Day, New Gravity Main 6km dia 150 mm, 3 No Storage Tanks	Marsabit	ADB/GOK	722,685,029	Sino Hydro Corporation	11/01/2018	05/01/2021	Marsabit Water and Sanitation Company	Contractor Mobilisation
Marsabit Sewerage project (Co-ordination)	Marsabit	Trunk sewer 4.7km dia ranging from 300-375mm, Secondary sewers 22.7km Dia 225mm, Sewerage treatment works capacity-5700m3/day	Marsabit	ADB/GOK	1,001,017,386	Sino Hydro Corporation	11/01/2018	05/01/2021	Marsabit Water and Sanitation Company	Construction works is at 5%.
Isiolo water Supply-Last Mile Connectivity (Co-ordination)	Isiolo	Laying of 18 Km of water pipeline of 110mm and 12 km DN 225mm sewer lines.	Isiolo	ADB/GOK	73,238,917	Dido Construction	29/11/18	29/11/20	Isiolo Water and Sanitation Company	Construction works is at 30%.

Garissa water and Sewerage - Last Mile Connectivity (Co-ordination)	Garissa	boreholes,Construction of 3 No.Large Diameter Wells,Construction of 1000m ³ RC storage tank and 8 Km of 250mm raising main,Construction of 1No elevated tank and Rehabilitation of pumping equipment.	Garissa	ADB/GOK	191,467,331	Concordia Construction	29/11/18	29/11/20	Garissa Water and Sanitation Company	Contractor Mobilisation
Meru Sewerage project	Meru Urban Centre	Construction of sewerage Treatment system with a capacity of 8,000m ³ ,trunk and secondary sewers of 36.5KM Ranging from 600-300mm Diameter pipes	Meru	ADB/GOK	874,506,524	Toddy Civil Engineering Ltd.	21/1/19	21/7/21	Meru Water and Sewerage Services	Contractor Mobilisation
Kianjuri Dam	Kibirichia inside Mt Kenya forest	Construction of an earth dam with a storage capacity 300,000 m ³	Meru	GOK	62,838,838	Kabco Limited	25/6/18	03/10/2019	Community	Construction works is at 15%
Thangatha Dam	Micii Mikuru inside Nyambene Forest	Construction of a concrete lined earth dam with a storage capacity 50,000 m ³	Meru	GOK	31,815,740	Ranju Limited	08/08/2018	02/08/2019	Community	Construction works is at 60%
Ndumuru Dam	Ndumuru location	Construction of a earth dam with a storage capacity 140,000m ³	Meru	GOK	20,000,000	AMG Sagirin	11/09/2018	02/06/2019	Community	Project substantially complete and it
Ura 4 Dam	Mukururu inside Nyambene Forest	Construction of a earth dam with a storage capacity 100,000m ³	Meru	GOK	58,271,400	AMG Sagirin	08/04/2018	02/04/2019	Community	Construction works is at 55%.
Buri Ya Antu	Kianjai Ward, Tigania West	Drilling of Borehole and equipping with sloar	Meru	GOK	5,000,000	Not awarded	-	-	Community	In tendering stage
Thumberia borehole	Njia Ward, Igembe Central	Drilling of Borehole and equipping with sloar	Meru	GOK	4,500,000	Not awarded	-	-	Community	In tendering stage
Makuyu dam	Makuyu Ward, Maragwa	Rehabilitation of Makuyu dam, Land scaping and Fencing	Murang'a	GOK	5,000,000	Not awarded	-	-	Community	In tendering stage
Mariari kirigara Dam	Kiambere Ward, Gachoka	Construction of a small earth Dam, draw off, cattle troughs and water point	Embu	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Itangi 2	Murinduko Ward, Mwea	Construction of a small water pan, draw off and fencing	kirinyaga	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Kagio Police Borehole	Mukuure Ward, Ndia	Drilling of Borehole and equipping with solar	kirinyaga	GOK	3,500,000	Not awarded	-	-	Community	In tendering stage
Riakania Borehole	Riakania Ward,Ndia	Drilling of Borehole and equipping with solar	kirinyaga	GOK	3,500,000	Not awarded	-	-	Community	In tendering stage
Mugumo dam	Ithanga, Gatanga	Construction os a small earth dam, draw off and fencing	Murang'a	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Iganjo Silanga	Kamahuha Ward, Maragwa	Construction os a small earth dam, draw off and fencing	Murang'a	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Bonden dam	Mweiga Ward, Kieni	Construction os a small earth dam, draw off and fencing	Nyeri	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Mugaka dam	Gatarakwa Ward, Kieni	Construction os a small earth dam, draw off and fencing	Nyeri	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Gwa Kagiri dam	Endarasa Ward, Kieni	Construction os a small earth dam, draw off and fencing	Nyeri	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Kianyange dam	Ruguru Ward, Mathira	Construction os a small earth dam, draw off and fencing	Nyeri	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Kiairanthi Rock Catchment	Gatunga Ward, Tharaka	Construction of rock catchment and storage tank	Tharaka Nithi	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage

Kithima Water Project	Chogoria Ward, Maara	Laying of main and distribution pipe network	Tharaka Nithi	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Kamwimbi dam	Kamwimbi Ward, Chuka	Construction os a small earth dam, draw off and fencing	Tharaka Nithi	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Ntumburi Borehole	Ntugi Ward, Buuri	Drilling of Borehole and equiping with solar	Meru	GOK	6,000,000	Not awarded	-	-	Community	In tendering stage
Sisi Kwa Sisi Water project	Mukothima Ward, Tharaka	Laying of main and distribution pipe network	Tharaka Nithi	GOK	20,000,000	Not awarded	-	-	Community	In tendering stage
Ndigia Water Project	Gitareni-Mugwe, Igamba Ngombe	Laying of main and distribution pipe network	Tharaka Nithi	GOK	20,000,000	Not awarded	-	-	Community	In tendering stage
Kamwene Water Project	Mitheru Ward, Maara	Laying of main and distribution pipe network	Tharaka Nithi	GOK	55,000,000	Not awarded	-	-	Community	In tendering stage
Mwichuri Water Project	Chogoria Ward, Maara	Laying of main and distribution pipe network	Meru	GOK	20,000,000	Not awarded	-	-	Community	In tendering stage
Wahundura/Kiringu water project	Kamacharia, Wahundura	Laying of main and distribution pipe network	Murang'a	GOK	20,000,000	Not awarded	-	-	Community	In tendering stage
Miathene Boys' High Sch. B/H	Tigania West	Drilling of Borehole and equiping with solar	Meru	GOK	10,000,000	Not awarded	-	-	Community	In tendering stage